Synthetic Tower - Bill of Quantities

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	DIVISION 03 - CONCRETE				
3.1	Cast-in-place concrete				
3.1.1	Plain concrete grade C15 blinding 50 mm thick	m3	86		
3.1.2	Reinforced concrete grade C35 to raft foundations, including formwork and curing	m3	1,240.50		
3.1.3	High-yield steel reinforcement bars	ton	1,250.00		
	* Rates shall include all testing				
	Total carried to summary				12,345.00

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	DIVISION 09 - FINISHES				
9.1.1	Porcelain floor tiles 600x600 mm	m2	2,300		
9.1.2	Skirting to match floor tiles (rate only)	L.M.			